RENDERING KEY

- EXISTING TREE TO REMAIN
- PROPOSED NEW TREE
- TREE TO BE TRANSPLANTED (TRANSPLANT LOCATION)

PLANTING NOTES:

1. LANDSCAPE CONTRACTOR (L.C.) TO CALL MISS. UTILITY BEFORE BEGINNING ANY WORK.
2. L.C. TO VERIFY ALL QUANTITIES & AVAILABILITY ON PLANT LIST BEFORE BIDDING AND/OR ORDERING ANY PLANTS. IN EVENT OF DISCREPANCY BETWEEN QUANTITIES SHOWN ON PLANTING PLAN TO THOSE SHOWN ON PLANT LIST, THOSE SHOWN ON PLANTING PLAN SHALL PREVAIL.
3. L.C. TO REMOVE INVASIVE VINES & SAPLINGS UNDER DIRECTION OF LANDSCAPE ARCHITECT (L.A.)
4. L.C. TO ADD MULCH RINGS UNDER ALL EXISTING AND NEW TREES

GENERAL NOTES

1. SITE PLAN PROVIDED BY CHEVY CHASE VILLAGE (SITE PLAN BASED ON PLAN BY G.L. RUPERT AND ASSOCIATES)
2. FOR LOCATION OF UTILITIES, CALL "MISS UTILITY" AT 1-800-257-7777, OR LOG ON TO WWW.MISSUTILITY.NET/TIC 48 HOURS IN ADVANCE OF ANY WORK IN THIS VICINITY. THE EXCAVATOR MUST NOTIFY ALL PUBLIC UTILITY COMPANIES WITH UNDER GROUND FACILITIES IN THE AREA OF PROPOSED EXCAVATION AND HAVE THOSE FACILITIES LOCATED BY THE UTILITY COMPANIES PRIOR TO COMMENCING EXCAVATION. THE EXCAVATOR IS RESPONSIBLE FOR COMPLIANCE WITH THE REQUIREMENTS OF THE LOCAL JURISDICTION.
3. ALL SUBSURFACE PIPES TO BE RIGID PVC PIPE.

KEY

	EXISTING TREES
	PROPERTY LINE
99.5	EXISTING ELEVATION
99.5	PROPOSED ELEVATION
100	EXISTING CONTOUR
100	PROPOSED CONTOUR
G	GAS
W	WATER
S	SEWER
OHL	OVERHEAD LINE
S	SANITARY MH
	POWER POLE
	LIGHT POLE
	SIGN
	EX. WOOD FENCE
	EX. METAL FENCE
	PROP. WOOD FENCE
TBT	TO BE TRANSPLANTED
TBR	TO BE REMOVED
LC	LANDSCAPE CONTRACTOR
GC	GENERAL CONTRACTOR
	HARDSCAPE TO BE REMOVED
	EXISTING MULCH RING

TYP. TREE PLANTING ON SLOPE
NOT TO SCALE

LILA FENDRICK landscape architecture & garden design
6904 West Avenue Chevy Chase, Maryland 20815 (301) 907-7700

NEWLANDS PARK
NEWLANDS STREET, CHEVY CHASE, MD 20815

06-17-14
10-03-14

NEWLANDS PARK
LANDSCAPE MASTER PLAN
1/16"=1'-0"

Plantings